CHITALDRUG DISTRICT.

Abstract Notification dated 29th April 1935.

It is hereby notified for general information that the exclusive right of collecting the Minor Forest produce on all Government unoccupied lands, Amrit Mahal Kavals, State Forests, Reserved lands and plantations to end of June 1936 from date of confirmation will be resold Taluk-war by public auction on the dates and at the places specified below at 2 P.M., at the risk of the original purchasers.

Taluk	Place of sale	Date of sale	Officer conducting the sale
1. Holalkere 2. Hosdurga 3. Molakalmuru	District Forest Office, Chitaldrug.	20th May 1935.	Deputy Commissioner, Chitaldrug or an Assistant Commissioner of Senior Rank deputed by him.

As regards the sale conditions, etc., please see the detailed notification No. D1-201—1302-33, dated 3rd May 1934, published in pages 563 to 567, Part VI of the *Mysore Gazette*, dated 10th May 1934.

D. N. MOORTY RAO,
District Forest Officer.

ENGINEERING DEPARTMENT

BUREAU OF SANITARY ENGINEERING, BANGALORE.

Abstract Notification dated 18—19*th April* 1935.

Attention of the public is invited to the notice calling for tenders for constructing an Office Building for the Superintendent, Kolar Gold Fields Water Works, Bethamangala, published on pages 926-927, Part VI of the *Mysore Gazette*, dated 25th April 1935.

The last date for receipt of tenders is 10th May 1935.

K. S. HUTCHA RAO,
For *Sanitary Engineer.*

BUILDINGS DIVISION, BANGALORE.

Abstract Notification dated 22nd April 1935.

The attention of the public is invited to the notification calling for tenders for constructing a building for Arrack and Toddy shops near Gubbi Theatre, Bangalore City, published on pages 928-929 of Part VI of the *Mysore Gazette*, dated 25th April 1935.

The last date of receiving tenders is 11th May 1935.

A. TANDONI RAO,
Executive Engineer.

HEADQUARTER RANGE, MYSORE.

Notification dated 2nd May 1935.

Notice is hereby given that sealed tenders will be received at the Office of the Assistant Engineer, Headquarter Range, at 12 noon on 13th May 1935 for Constructing a New Office for the Superintendent, Power and Light, Mysore. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of 1935.

2. The plans, detailed estimate and conditions may be seen at the Assistant Engineer's Office at Mysore once between the hours of 11 A.M. to 5 P.M.

3. Tender should be submitted on printed forms which may be obtained from the Assistant Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a depoist of Rs. 300 (three hundred) in cash in the 1st instance and to be raised to Rs. 500 by the successful tenderer ofter acceptance as earnest money, and be superscribed "Tender for constructing a new office for the Superintendent, Power and Light, Mysore," in default of which, the tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Assistant Engineer's Office in due course. No enquiry regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Rates once tendered will not be enhanced on any account.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the Department or those fixed by the Assistant Engineer after working out data with not more than 10 per cent for contractor's profit.

11. In all matters not specifically provided for and in all matters of dispute about rates, quantities, measurements, quality of work, etc., and in all disputes of any kind, the decision of the Superintending Engineer will be final and legally binding.

12. Tenders must be given in words as well as in figures and they must be in specific term of unit shown against each item of work. Any quotation quoted at so much percentage less or more than estimated or lowest tender rate will not be accepted.

13. Old materials available such as windows, doors,, etc. must be used, only fixing charges being paid.

14. Progress to the extent of Rs. 10,000 should be made before the 25th June 1935 and work completed in all respects by the 1st week of August 1935.

Abstract estimate for Constructing a New Office for the Superintendent, Power and Light, Mysore.

No.	Items of work	Unit	Rate	Quantity	Cost
			Rs. a. p.		
1	Earthwork excavation and filling in basement ..	C.yds.		438	
2	Stone jelly concrete in chunam mortar ..	C.ft.		1,894	
3	Foundation size stone in chunam mortar ..	C.ft.		6,158	
4	Basement size stone in mortar face dressed ..	,,		1,408	
5	Burnt stone slab 6″ thick rough dressed ..	S.ft.		1,420	
6	Two line dressing	,,		832	
7	Superstructure burnt brick in mortar ..	C.ft.		5,470	
8	Pillars in verandah ordinary brick in cement mortar with bond stone with plastering including base and capital etc., complete 11 ft. high	No.	..	15	
9	Providing and fixing teakwood door with frame and panelled shutters $1\frac{1}{4}$″ thick including iron fitting bolts etc., complete with ventilator tops	S.ft.		586.56	
10	Providing and fixing teakwood windows with frame and glazed shutters with iron bar $\frac{3}{4}$″ dia. and iron fittings (hinges and bolts etc.) complete.	,,		370.50	
11	Providing and fixing stone brackets in front as per design with bearing slabs etc., complete below sun shade	No.		6	
12	Burnt stone slab 6″ with three line dressing complete	S.ft.		135	
13	Providing hoisting and fixing R. S. girders British standard and tested including one coat of anticorosive or other paint	Cwt.		67.56	
14	3″ cement concrete plaster 1 : 2 : 4	S.ft.		331	
15	Teakwood wrought and put up including wood oiling	C.ft.		396	
16	Pucca terrace with one course of brick on edge, one course of brick on flat with 3″ of kappi and 2 courses of flat tiles with top and bottom plastered etc., complete	Sqr.		26.71	

No.	Items of work	Unit	Rate	Quantity	Cost
			Rs. a. p.		
17	Flooring with first class Mangalore square tiles on 3″ of chunam concrete bed with cement pointing etc., complete	Sqr.		21.89	
17(*a*)	Flooring with $1\frac{1}{2}$″ C.C. ($1 : 2\frac{1}{2} : 5$) over 3″ ordinary concrete and $\frac{1}{2}$″ cement plaster finished to tile pattern with red colour	,,		21.89	
18	Chunam plastering	,,		70.31	
19	White and colour washing	,,		70.31	
20	Band cornice 4″ to 6″ depth as per design ..	R.ft.		62	
21	Parapet wall 3′ high and 9″ thick plain with base, top cornice, including plastering etc., complete as per design	,,		250	
22	Painting the doors and windows with two coats of 'Duco' paint	Sqr.		18.76	
23	Cement pointing to basement	,,		5.05	
24	Providing and fixing C. I. pipe 6″				
24	Providing and fixing C. I. pipe 6″ dia. including bends, elbows etc., complete	R.ft.		264	
25	Ornamental pendents in mortar as per design ..	No.		4	
26	Boxing up girders with terrace bricks in cement mortar with ordinary plastering and underside cement plaster				
	(*a*) 18″×7″ and 20″×$6\frac{1}{2}$″	R.ft.		74	
	(*b*) 6″×3″ double	,,		105	

Notification dated 3rd May 1935.

Notice is hereby given that sealed tenders will be received at the Office of the Assistant Engineer, Headquarter Range, Mysore, up to 4 P.M. on 18th May 1935 for Improving the Arcot tiled roofing, etc., in the Exhibition Building at Mysore. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of July 1935.

2. The plans, may be seen at the Assistant Engineer's Office at Mysore once between the hours of 11 A.M. and 5 P.M. on working days

3. Tender should be submitted on printed forms which may be obtained from the Assistant Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 50 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for improving the Arcot tiled roofing, etc., in the Exhibition Building at Mysore" in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Chief Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Assistant Engineer's Office, in due course. No enquiry regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Rates once tendered will not be enhanced on any account.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the Department or those fixed by the Assistant Engineer after working out data with not more than 10 per cent for Contractor's profit.

11. In all matters not specifically provided for and in all matters of dispute about rates, quantities, measurements, quality of works, etc., and in all disputes of any kind, the decision of the Superintending Engineer will be final and legally binding.

12. Quotations must be given in words as well as in figures and they must be in specific term of unit shown against each item of work. Any quotation quoted at so much percentage less or more than estimated rate will not be accepted.

13. Old materials available such as windows, doors, etc., must be used, only fixing charges being paid.

Estimate for improving the existing arcot-tiled roof and putting up a terrace verandah, etc., in the Exhibition Buildings at Mysore.

No.	Items of work	Unit	Rate	Quantity	Cost
			Rs. a. p.	Quantities for all the blocks.	
1	Removing the existing arcot-tiled roof with flat tiles and stacking the same including carting to Stores	Sqr.		145·60	
2	Removing and stacking teakwood work and fixing	C.ft.		1,145	
3	Raising old pillars with burnt brick in mortar ..	,,		1,228	
4	Raising wall with burnt brick in mud ..	,,		5,970	
5	Dismantling the existing mud wall and constructing brick in mortar pillars 11′ heig with foundation of 2′×2′ concrete and basement plastering and bearing slab two-lined, dressed, etc., complete	Each		91	
6	Constructing masonry pillars with cement burnt brick in mortar in verandah $1\frac{1}{8}'\times1\frac{1}{8}'\times7'$ including foundation and basement, etc., complete, with plastering	,,		91	
7	Rolled steel girders of British standard of 4″×7″ of 16 lbs.	Cwt.		288	
8	Teakwood work wrought and put up including two coats of wood oiling	C.ft.		616·74	
9	Boxing up girders with terrace bricks and plastering, etc., complete	R.ft.		2,290	
10	Roofing with pukka terrace with two courses of flat tiles and plastering, etc., complete ..	Sqr.		100·06	
11	Roofing with 1st class Mangalore tiles on teak reepers, etc., complete	Sqr.		154·70	
12	Providing mortar bands	L. S.		..	
13	Band cornice with ordinary moulding as per design to be given	R.ft.		1,380	
14	Providing and fixing ridge tiles set in mortar ..	,,		910	
15	Providing teakwood eave board 7″×1″ including chocolate painting	,,		1,820	
16	Parapet wall plain $\frac{3}{4}\times\frac{3}{8}$ (as per design to be given) 2′ high complete with pillasters and coping, etc., complete with 3″ string course..	,,		1,380	
17	Chunam plastering	Sqr.		110·00	
18	Whitewashing	L. S.		..	
19	Rain water down take pipes 4″ diameter and 3′ long including fixing spouts	R.ft.		120	
20	Flooring with 3″ ordinary concrete and $1\frac{1}{2}$″ cement concrete 1 : 2 : 5 with $\frac{1}{2}$″ cement plaster 1 : 3 including colouring and finishing to tile pattern	Sqr.		177·98	
21	Dismantling the existing burnt stone flooring and removing them	,,		45·75	
22	Curbing the road edges with burnt stone slabs removed including earthwork splitting ..	R.ft.		3,100	
23	Extra earthwork filling in foot-paths including carting	C.yds.		459	
24	Covering the drain in front :—				
	(*a*) Burnt brick in mud for side walls of drain .	C.ft.		930	
	(*b*) Cement plastering, $\frac{1}{2}$″ thick	Sqr.		7·75	
	(*c*) Dry stone pitching for bed of drain ..	C.ft.		155	
	(*d*) Covering the top with cuddapah slabs available from dismantled floor of fine arts section	S.ft.		775	
	(*e*) Earthwork excavation for side walls ..	C.yds.		17	

No.	Items of work	Unit	Rate	Quantity	Cost
			Rs. a. p.		
	II. Putting up new pukka stalls on the site of the old domestic basin demonstration shed.				
1	Dismantling existing roof and carting to Stores	Sqr.		20·20	
2	Teakwood wrought and put up	C.ft.		90	
3	Roofing with corrogated asbestos sheet roofing, complete	Sqr.		25·84	
4	Providing iron brackets with bolts and nuts, etc., complete, including fixing	Cwt.		4	
5	Flooring with 1½" cement concrete over 3" ordinary jelly concrete and cement plaster mixed with red colour and cut to tile pattern ..	Sqr.		12·30	
	III. Improving in fine arts section by removing arch ways.				
1	Providing and fixing R. S. joists for lintels over openings	Cwt.		48	
2	Dismantling brick masonry in arch ways ..	C.ft.		856	
3	Chunam plastering smooth sides of opening dismantled	Sqr.		10·22	
4	Providing and fixing cement fret work for ventilators	S.ft.		258	
5	Providing and fixing glasses outside to prevent rain water	,,		258	

N.B.—The above quantities are for blocks in the exhibition premises and are not guaranteed. The distribution will be made among different contractors for speedy execution of work.

S. RAMASWAMY,
Assistant Engineer.

SHIMOGA FOREST DIVISION.

Notification dated 1st May 1935.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Shimoga Division, up to 2 P.M., on 15th May 1935, for restoring Udagani Herekere, Reg. No. 1138, Shikarpur Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of October 1935.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Shimoga between the hours of 11 A.M. to 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a Treasury Challan for having deposited Rs. 150 (one hundred and fifty only) as earnest money, and be superscribed "Tender for restoring Udagani Herekere, Reg. No. 1138, Shikarpur Taluk" in default of which tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiry regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Rates once tendered will not be enhanced on any account.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the department or those fixed by the Executive Engineer after working out data with not more than 10 per cent for contractor's profit.